

Northampton District Scouts - Asbestos Register										Survey Type: - Management					
Site: - Overstone Scout Campsite & Activity Centre										Date of Survey: - December 2021					
Business Unit	Floor	Room	Position	Description	Fibre Type	Comment	Assessment Date	Product Type	Extent m <sup>2</sup> (m <sup>2</sup> area) (l = length)	Condition	Material Risk Assessment	Priority Risk Assessment	Overall Risk	Overall Risk Category	Recommendation
Pack Holiday Centre	Ground	00006	Above Ceiling tiles and Extern	Disused Flue	Chrysotile	Good condition - above ceiling tiles	4 Dec 2021	Cement	2(l) & 3(l)	Good	3	1	4	Minor	Leave in situ and inspected routinely
Pack Holiday Centre	First	01002	Water Tank	Gasket	Chrysotile	Within pipe work	4 Dec 2021	Gasket	<1	Good primarily encased	2	1	3	Minor	Leave in situ and inspected routinely
Pack Holiday Centre	First	External	Undercloak to Roof	Cement Lining	Chrysotile	Good condition not readily accessib	4 Dec 2021	Cement	40(l)	Mainly in good condition	2	1	3	Low	Leave in situ and inspected routinely
The Royal Building	Ground	00001-00005	Wall	Lining	Chrysotile & Amosite	Lining Board	4 Dec 2021	Cement Board	60	Good Sealed	3	5	8	Low	Leave in situ and inspected routinely
The Royal Building	Ground	00001-00005	Ceiling	Lining	Amosite and Crocidolit	Lining Board	4 Dec 2021	Cement Board	36	Good Sealed - Slight Bowing	4	4	8	Low	Leave in situ and inspected routinely
The Royal Building	Ground	External	Wall	Lining	Chrysotile	Lining Board	4 Dec 2021	Cement Board	36	Weathered some presumed behind timber cladd	2	1	3	Minor	Leave in situ and inspected routinely
Blackthorn Hub+A1			No ACMs Detected within the Remit of an Asbestos Management Survey			Textured Coated Ceiling	4 Dec 2021				0	0	0		Undertake R&D should any Refurbishment be planned
Will Smith Building			No ACMs Detected within the Remit of an Asbestos Management Survey			Sink Pad	4 Dec 2021				0	0	0		Undertake R&D should any Refurbishment be planned
Tractor Shed / Workshop			No ACMs Detected within the Remit of an Asbestos Management Survey				4 Dec 2021				0	0	0		Undertake R&D should any Refurbishment be planned
Maintenance Portacabin - Green			No ACMs Detected within the Remit of an Asbestos Management Survey				4 Dec 2021				0	0	0		Undertake R&D should any Refurbishment be planned
Wood land Bottom Shelter			No ACMs Detected within the Remit of an Asbestos Management Survey				4 Dec 2021				0	0	0		Undertake R&D should any Refurbishment be planned
BBQ Shelter			No ACMs Detected within the Remit of an Asbestos Management Survey			-	4 Dec 2021				0	0	0		Undertake R&D should any Refurbishment be planned
Top Field Shelter			No ACMs Detected within the Remit of an Asbestos Management Survey			-	4 Dec 2021				0	0	0		Undertake R&D should any Refurbishment be planned
2000s Toilet Block			No ACMs Detected within the Remit of an Asbestos Management Survey			-	4 Dec 2021				0	0	0		Undertake R&D should any Refurbishment be planned
Main Fire Shelter			No ACMs Detected within the Remit of an Asbestos Management Survey			-	4 Dec 2021				0	0	0		Undertake R&D should any Refurbishment be planned
Blackthorn Woods Toilets	Ground	Girls	Floor	Thermoplastic Floor Tile	Chrysotile	Grey Floor Tiles	4 Dec 2021	Thermoplastic	<1	Good	6	4	10	Low	Door Lining - Licensed if Work required
Blackthorn Woods Toilets	First	External	Roof	Corrugated Cement	Chrysotile	Good condition not readily accessib	4 Dec 2021	Cement	40(l)	Weathered	2	1	3	Low	Leave in situ and inspected routinely